



---

# SFBP Station Boat No. 1

*Preliminary Authorization Request*

CA Board of Pilot Commissioners | March 26, 2026

---



110' Hybrid Pilot Station Vessel • EPA Tier 4 + DPF • 20-Year Service Life



# Agenda

## *Station Boat No. 1 — Preliminary Authorization*

- 1 Vessel Design and Particulars
- 2 Shipyard and Contracting
- 3 Project Management
- 4 Legal Considerations
- 5 Financing Structure
- 6 Cost and Contract Structure
- 7 Cost Summary
- 8 Preliminary Authorization Request



# Vessel Characteristics

## Principal Dimensions, Specifications & Key Features

<b>LOA</b>	110'
<b>Beam</b>	28.1'
<b>Draft</b>	9'
<b>Full Load Displacement</b>	257 LT
<b>Lightship Weight</b>	205 LT
<b>Structural Steel Weight</b>	97 LT
<b>Speed</b>	12 kts cruise, 15 kts max
<b>Accommodations</b>	4 crew, 8 pilots
<b>Regulatory</b>	Uninspected, unclassified, ABS load line



### Key Design Features

#### Extended Hull

104 to 110 ft to accommodate CARB mandated emissions equipment

#### Hybrid Propulsion

Parallel hybrid with PTO/PTI motors for cleaner operation

#### Energy Storage

240 kWh lithium-ion ESS for pier-side and loiter power


#### Emission Controls

SCR + DPF on engines and generators



# General Arrangement

## Outboard Profile




Outboard Profile — 110' LOA with extended hull with hybrid propulsion



# General Arrangement

## Main Deck Plan




Main Deck Plan — Pilothouse, galley, lounge/mess, and back-deck work area with daughter boat stowage



# General Arrangement

## Below-Deck Plan



Below-Deck Plan — Engine room, battery room with HVAC/fire suppression, forward berthing, and tank layout





# Daughter Boat

*Auxiliary Operations Vessel*



*Built by Safeboats International*

## Key Functions

### ■ Man Overboard

Primary MOB rescue and recovery operations

### ■ Odd Vessels

Transfer pilots to/from vessels too small or positioned for the 110-ft station boat

### ■ Close-Quarters

Maneuvering in tight anchorages and alongside difficult hull configurations



# Propulsion & Steering

## *Arrangement Overview*



### **Main Engines & Drivetrain**

Two main engines with close-coupled gearboxes mated to straight shafts driving 5-bladed propellers for optimal thrust and efficiency.



### **Steering System**

Twin rudders provide precise steerage and maneuverability in the demanding conditions of San Francisco Bay.



### **Control Stations**

Propulsion and steering controlled from four stations: one on each side of the pilothouse and one on either side of the back deck.



# Main Engines

## *EPA Tier 4 MAN 30-Liter Diesel Engines*

### ■ Engine Configuration

Two EPA Tier 4 MAN 30-liter diesel engines with integrated SCR + DPF emission controls

### ■ Drive System

Straight shafts drive 5-bladed propellers for optimal thrust and efficiency

### ■ Gearbox & Coupling

Close-coupled to 4:1 clutched reduction/trolling gearboxes with rubber coupling for noise reduction


### ■ Emission Controls

Compact passive Diesel Particulate Filters (DPF) installed in the engine room



# Main Engines

## *Engine and Drivetrain Configuration*



*Main engine with close-coupled gearbox, PTO/PTI motor, and Lo-Rez shaft vibration isolation system*



# Electrical System

## *Power Distribution Architecture*

### ■ DC Bus

Ship service gensets supply power directly to a ~750 VDC bus

### ■ Main Switchboard

208 VAC 3-phase switchboard powers hotel loads through bidirectional inverter

### ■ AC Distribution

Subsidiary AC power panels in the pilothouse, fan room, and galley

### ■ Bridge Batteries

12 VDC and 24 VDC battery banks support vital electrical systems on the bridge

### ■ Engine Batteries

Two 24 VDC battery systems power vital engine controls, starters, and steering

### ■ Charging

Each battery bank is continually charged from the AC bus for redundancy



# Gensets

## *Electrical Power Generation*

1

### **Generator Sets**

Two Northern Lights variable-speed 200 kW gensets using Danfoss permanent magnet alternators for reliable power generation

2

### **DC Bus Integration**

Generators supply power through rectifiers directly to the main DC bus for efficient distribution

3

### **Emission Filtration**

Generator exhaust filtered by Diesel Particulate Filters (DPF) to meet environmental requirements



# Energy Storage System

## *Marine Lithium-Ion Battery Packs*

240

kWh Capacity

- Marine lithium-ion battery packs installed as part of the electrical integrator's scope

---

- Supports hotel loads on the pier, meets power demands when a second genset comes online, and powers propulsion during loiter operations

---

- Housed in a dedicated battery room with HVAC, firefighting, and gas detection systems



# Wheelhouse Design

*Enhanced Situational Awareness & Navigational Safety*

*Ergonomic bridge layout based on the configuration our captains already operate, with targeted improvements to increase safety and efficiency.*



## Solid-State Radar

Enhanced target detection and reliability for fog-prone San Francisco Bay operations



## Integrated Monitoring System

Centralized display of propulsion, auxiliary systems, tanks, CCTV, and weather data



## FLIR Infrared Camera

Improved detection in low-light and reduced-visibility conditions; supports search and MOB recovery



## Man Overboard Detection

Rapid automated alerting and GPS tracking for improved MOB response capability



# Onboard Improvements

*Crew Safety, Comfort & Environmental Stewardship*



## Noise & Vibration Reduction

Pilothouse, lounge/mess, and forward berthing designed to  $\leq 65$  dB(A). Floating floors and isolation mounts. Acoustic treatment throughout.



## Hybrid Propulsion

Cleaner, quieter propulsion reducing emissions. Main engines secured during loitering with electric power. Extended maintenance intervals.



## HVAC & Air Quality

Modern climate control with high fresh-air exchange rates and advanced filtration throughout all crew and operational spaces.



---

# Shipyard & Contracting

---



# Nichols Brothers Boat Builders

*Located in Freeland, WA — Whidbey Island*



60+ years of U.S. shipbuilding experience



Tugs, workboats, and ferries



200+ vessels delivered



Experience with California emissions requirements



*Representative vessel rendering — Station Boat No. 1*



# NBBB – Primary Construction Space

*Shipyard Facility Overview*



*NBBB primary construction facility — covered fabrication building*



# NBBB Fabrication Space

*Steel Fabrication and Assembly*



*NBBB fabrication and assembly workspace*



# NBBB – WETA Ferry

*Recent Construction Projects*



*WETA all-electric aluminum ferry under construction*



# Construction Schedule

*Anticipated 18–22 Month Build Period*



**Contract Signing:** June 2026    **Construction Start:** Sept 2026    **Delivery:** Q1 2028

**Total Build Period: 18–22 Months**



---

# Project Management

---



# Maritime Consulting Partners

*Project Management Partner*

## MARITIME CONSULTING PARTNERS

[maritimeconsultingpartners.com](http://maritimeconsultingpartners.com)

*Pacific Northwest*

- Extensive experience in marine engineering, program development, and project management
- Engaged on PV Golden Gate project and WETA ferry projects
- Well versed in CARB regulations
- Based in the Pacific Northwest



# Project Management Details

## *Scope of Services*

- 1 Administration of the VCA, ensuring shipyard compliance
- 2 Schedule review, oversight, and day-to-day monitoring of progress and quality
- 3 Review of all payment requests and technical/pricing evaluation of change orders
- 4 Drawing and deliverable review for specification compliance

- 5 Attendance at project kick-off, weekly, quarterly, and design review meetings
- 6 Witness all shipyard testing and quality checkpoints; in-process inspections
- 7 Attendance at all Dock, Sea, and Acceptance Trials with deficiency documentation
- 8 Shipyard close-out: review of final deliverables (manuals, as-builts, reports)



# Legal

## *Anticipated Legal Costs*

### 1 Construction Agreement

---

Negotiation and execution of Vessel Construction Agreement between SFBP B&P and NBBB

### 3 Lender Fees

---

SFBP B&P responsible for legal fees incurred by Five Star Bank in loan initiation (standard lender practice)

### 2 Line of Credit

---

Negotiation and execution of Vessel Construction Line of Credit between SFBP B&P and Five Star Bank

### 4 Construction Monitoring

---

Monitoring of construction and delivery: confidentiality, risk of loss transfer, and warranty issues



# Financing Structure

## *Construction Line of Credit*

# LOC

## Construction Line of Credit

- Tax implications of receiving revenue without depreciation offset — requires debt-first, accrual-match strategy
- Milestone-based disbursements tied to verified progress
- Funds released only when construction milestones are met
- Aligns financing with responsible stewardship of funds



# Cost & Contract Structure

## *Milestone-Based Disbursements*

1

### Define

Clearly defined milestones and approval processes

2

### Verify

Milestone-based disbursements tied to verified progress

3

### Release

Funds released only when construction milestones are met

4

### Steward

Aligns financing with responsible stewardship of funds



# Cost & Contract Structure

## *NBBB Contract Overview*



### **Fixed-Price Contract**

Fixed-price construction contract (~\$24M) with clearly defined scope and specifications



### **Performance Bond**

Performance bond included to protect SFBP B&P investment throughout construction



### **Change-Order Process**

Formal change-order process ensures transparency and cost control on all modifications



### **Quality Control**

Formal quality control processes with documented inspections at every milestone



# Milestone Payment Schedule - CONFIDENTIAL

*Construction Progress-Based Disbursements (1 of 2)*

#	Milestone Description	Est. Date	%	Amount
1	Contract Sign	6/1/2026	10%	\$2,329,453
2	Receipt of Cut Part Information	7/16/2026	5%	\$1,164,727
3	Steel Delivery	9/15/2026	5%	\$1,164,727
4	Steel Delivery 2	10/16/2026	5%	\$1,164,727
5	Bow Module Structure 95%	12/8/2026	5%	\$1,164,727
6	Engine Room Module 95%	12/22/2026	5%	\$1,164,727
7	Engineering 95% Complete	12/29/2026	5%	\$1,164,727
8	Superstructure Module Complete	1/23/2027	5%	\$1,164,727
9	Hull Modules Joined	2/13/2027	5%	\$1,164,727
10	Pipe Spools 50% Complete	3/16/2027	5%	\$1,164,727

**Subtotal Milestones 1–10: \$13,962,178**



# Milestone Payment Schedule - CONFIDENTIAL

*Construction Progress-Based Disbursements (2 of 2)*

#	Milestone Description	Est. Date	%	Amount
11	Hull Painted	4/24/2027	5%	\$1,164,727
12	Main Engines and Gears Received	6/11/2027	5%	\$1,164,727
13	Cooling, Fuel, Bilge & Air Installed	7/12/2027	5%	\$1,164,727
14	Engines, Shaft, Prop & Rudder	7/31/2027	5%	\$1,164,727
15	Danfoss Equipment Received	8/13/2027	5%	\$1,164,727
16	Pilothouse Outfitting 95%	9/27/2027	5%	\$1,164,727
17	Stage 2 Testing Complete	11/27/2027	5%	\$1,164,727
18	Delivery to San Francisco	1/10/2028	5%	\$1,164,727
19	Acceptance Trials Complete	2/19/2028	5%	\$1,164,727
	<b>Total (All 19 Milestones)</b>		<b>100%</b>	<b>\$23,294,531</b>



# Five Star Bank

*Line of Credit Partner*

## Bank Overview

### Founded

California-based business bank, est. 1999  
(NASDAQ: FSBC)

### Bauer Financial

Superior Rating — 5 Stars

### Findley Report

Super Premier Performer

### IDC Rating

Superior

### SBA Status

Preferred SBA lender

## Proposed Terms

### Rate

Prime + 0% (currently 6.75%)

### Interest

Only on funded balances

### Loan Fee

0.75%

### Good Faith Deposit

~\$33K (applied to closing costs)

### 3rd Party Costs

TBD — parties work to minimize



# Milestone Payment Schedule + Financing

Construction Progress-Based Disbursements (1 of 2)

CONFIDENTIAL

#	Milestone Description	Est. Date	%	Amount	Period Interest	Acc. Interest
1	Contract Sign	6/1/2026	10%	\$2,329,453	\$0	\$0
2	Receipt of Cut Part Information	7/16/2026	5%	\$1,164,727	\$19,655	\$19,655
3	Steel Delivery	9/15/2026	5%	\$1,164,727	\$38,654	\$58,309
4	Steel Delivery 2	10/16/2026	5%	\$1,164,727	\$27,080	\$85,389
5	Bow Module Structure 95%	12/8/2026	5%	\$1,164,727	\$56,780	\$142,169
6	Engine Room Module 95%	12/22/2026	5%	\$1,164,727	\$18,344	\$160,514
7	Engineering 95% Complete	12/29/2026	5%	\$1,164,727	\$10,701	\$171,215
8	Superstructure Module Complete	1/23/2027	5%	\$1,164,727	\$41,930	\$213,145
9	Hull Modules Joined	2/13/2027	5%	\$1,164,727	\$39,310	\$252,454
10	Pipe Spools 50% Complete	3/16/2027	5%	\$1,164,727	\$72,067	\$324,522

**Subtotal Milestones 1–10: \$13,962,178**



# Milestone Payment Schedule + Financing

Construction Progress-Based Disbursements (2 of 2)

CONFIDENTIAL

#	Milestone Description	Est. Date	%	Amount	Period Interest	Acc. Interest
11	Hull Painted	4/24/2027	5%	\$1,164,727	\$91,285	\$415,807
12	Main Engines and Gears Received	6/11/2027	5%	\$1,164,727	\$123,170	\$538,977
13	Cooling, Fuel, Bilge & Air Installed	7/12/2027	5%	\$1,164,727	\$88,010	\$626,987
14	Engines, Shaft, Prop & Rudder	7/31/2027	5%	\$1,164,727	\$58,091	\$685,078
15	Danfoss Equipment Received	8/13/2027	5%	\$1,164,727	\$42,585	\$727,663
16	Pilothouse Outfitting 95%	9/27/2027	5%	\$1,164,727	\$153,744	\$881,407
17	Stage 2 Testing Complete	11/27/2027	5%	\$1,164,727	\$222,754	\$1,104,161
18	Delivery to San Francisco	1/10/2028	5%	\$1,164,727	\$169,031	\$1,273,192
19	Acceptance Trials Complete	2/19/2028	5%	\$1,164,727	\$161,824	\$1,435,016
	<b>Total (All 19 Milestones)</b>		<b>100%</b>	<b>\$23,294,531</b>		<b>\$24,729,547</b>

**Total All 19 Milestones: \$24,729,547**



# Construction Cost Breakdown

*Price Breakdown by WBS Category*

CONFIDENTIAL

Category	Price
General Design and Construction Requirements	\$4,302,922
Delivery to San Francisco and Acceptance Trials	\$235,833
Structure	\$1,913,941
Propulsion Plant	\$3,096,046
Electrical	\$3,969,282
Communications, Navigation, and Ship Control	\$1,229,388
Machinery	\$4,577,106
Outfitting	\$3,280,013
<b>Total</b>	<b>\$23,294,531</b>



# Supplementary Costs

## *Additional Project Expenses*

### ■ Project Management

MCP & ad hoc engineering and onsite technical consultant services

### ■ Pre-Contract Engineering

Additional design phase engineering for 30L MAN engines

### ■ SFBP Oversight

Travel and lodging for pilot staff during construction oversight

### ■ Legal & Finance

Attorney fees for contract negotiation, loan initiation, and monitoring

### ■ Owner-Supplied Equipment

Miscellaneous equipment provided directly by SFBP for vessel outfitting

### ■ Fuel

Fuel costs for sea trials, delivery transit, and commissioning operations



# Total Estimated Construction Costs

## Station Boat No. 1 — Cost Summary

Item	Estimated Cost
Shipyard base contract	\$23,294,531
Engine change (est. adjustment)	\$250,000
Change order allowance (2%)	\$466,000
Daughter boat contract (Safeboats)	\$256,000
Miscellaneous owner-supplied items	\$50,000
Contingency for Fuel	\$45,000
Construction management (MCP)	\$750,000
Ad hoc engineering support	\$250,000
Pilot and staff travel/expenses	\$150,000
Legal	\$50,000
Interest and bank fees – Not Capitalized	\$1,500,000
<b>Total Construction Cost</b>	<b>\$27,061,531</b>

# Preliminary Authorization Request

*BOPC Joint PV Finance Committee | Construction Phase*

1

## **Project Approval**

Approval of the proposed Station Boat No. 1 project as presented

2

## **Contracting Authorization**

Authorization to proceed with shipyard contracting and financing

3

## **Cost Authorization**

Approval of total estimated construction costs of \$27.1M

*Note: Design and engineering subject to change. Costs and scheduling are best estimates.*



## Station Boat No. 1 — Ready to Proceed

**\$27.1M**

Total Estimated Cost

**110'**

LOA Hybrid Vessel

**20 Yr**

Planned Service Life

**Q1 2028**

Estimated Delivery